BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/09/2013-14, Date: 10.12.2013 **ITEM NO:17**

SCHEDULE-B

NAME OF WORK: Ward Maintanance for Gangmens & Tractor for 2nd shift 2.00PM to 10.00PM Removing silt & debries in the drains road side burms in Dasarahalli ward No 15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **K JAYAMMA**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	5657.4	90.5	Rupees Ninety and Fifty Paise Only
2	Clearing and grubbing road land including uprooting rank vegetating, grass, bushes, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials with a lead of 100 metres from road boundary, labour charge complete as per specifications.	Sqm	8297.4	4.5	Rupees Four and Fifty Paise Only
3	Providing JCB to Ward maintenance complete as per specifications.	Days	30	6031.0	Rupees Six Thousand Thirty One Only
4	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 15 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications.	Cum	5657.4	81.0	Rupees Eighty One Only

Jayamma K

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,